

Legrand cabling system LCS² category 5e

patch panels, blocks of connectors

NEW



335 52



335 90



335 55



Connecteur cat. 5e FTP

Pack	Cat.Nos	Patch panels cat. 5e 24 x RJ 45 connectors
		Panels supplied with quick mounting All enclosures or cabinets general assembly Panels ensure automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Fitted with 4 units of 6 LCS ² RJ 45 connectors cat 5e with fast connection thanks to integrated crimping, with 568 A/B labelling Supplied with colour labels numbered from 1 to 24 Conform to standards ISO/IEC 11801 Ed. 2.0, EN 50173-1 and EIA/TIA 568 19" panel - 1 U
1	335 51	UTP panel UTP panel - 8 contacts
1	335 52	FTP panel FTP panel - 9 contacts
		UTP through panel 24 RJ 45 connectors
1	335 88	UTP through panel

Pack	Cat.Nos	Modular panels
		Panels supplied with fast assembly All enclosures or cabinets general assembly Panels ensure automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Modular empty panels for up to 4 units Takes the following equipment: - units of 6 LCS ² RJ 45 connectors - units for telephone inlets - fibre optic units - PoE injector units - video streaming units - switch units - telephone/Ethernet doubler units - copper/fibre optic converter units - blanking plates 19" panel - 1 U
1	335 90	
1	xxx xx	19" angled panel - 1 U

Pack	Cat.Nos	Units of 6 x RJ 45 connectors cat. 5e
		Fitted with 6 x LCS ² RJ 45 connectors cat. 5e with fast connection thanks to integrated crimping, with 568 A/B labelling Supplied with colour labels Conforms to standards ISO/IEC 11801 Ed. 2.0, EN 50173-1 and EIA/TIA 568
2	335 54	UTP unit
2	335 55	FTP unit
10	335 91	Blanking plate for 19" panel - Black

Legrand cabling system LCS² category 6

patch panels, blocks of connectors

NEW



335 62



335 90



335 65



Connecteur cat. 6 STP blind

Pack	Cat.Nos	Patch panels cat. 6 24 x RJ 45 connectors
		Panels supplied with quick-fixing All enclosures or cabinets general assembly Panels ensure automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Fitted with 4 units of 6 LCS ² RJ 45 connectors cat. 6 connection with 110 tool, with 568 A/B labelling Supplied with colour labels numbered from 1 to 24 Conform to standards ISO/IEC 11801 Ed. 2.0, EN 50173-2 and EIA/TIA 568 19" 1 U panels
1	335 61	UTP panel - 8 contacts
1	335 62	FTP panel - 9 contacts
1	335 63	STP panel - metal shielding 360°
		UTP through panel 24 x RJ 45 connectors
1	335 89	UTP through panel

Pack	Cat.Nos	Modular panels
		Panels supplied with quick-fixing General all-purpose assembly of all enclosures or cabinets Panels ensure automatic earthing of each connector Fitted with rear cable guide to hold cables during maintenance Empty panels to be fitted with 4 units Take the following equipment: - 6 LCS ² RJ 45 connector units - telephone inlet units - fibre optic units - PoE injector units - video streaming units - switch units - telephone/Ethernet doubler units - copper/fibre optic converter units - blanking plates 19" panel - 1 U
1	335 90	
1	xxx xx	19" angled panel - 1 U

Pack	Cat.Nos	Units of 6 x RJ 45 connectors cat. 6
		Fitted with 6 x LCS ² RJ 45 connectors cat. 6 with fast connection thanks to integrated crimping, with 568 A/B labelling Supplied with colour labels Conform to standards ISO/IEC 11801 Ed. 2.0, EN 50173-1 and EIA/TIA 568
2	335 64	UTP unit - 8 contacts
2	335 65	FTP unit - 9 contacts
2	335 66	STP unit - metal shielding 360°
10	335 91	Blanking plate for 19" panel - Black

Legrand cabling system LCS² category 6A

patch panels, blocks of connectors

NEW



335 73



335 90



335 76



Connector cat. 6A shielded STP

Pack	Cat.Nos	Patch panel cat. 6A 24 x RJ 45 connectors
		Panel supplied with quick-fixing All enclosures or cabinets general assembly Panel ensures automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Fitted with 4 units of 6 LCS ² RJ 45 connectors cat. 6A with fast connection thanks to integrated crimping, with 568 A/B labelling Supplied with numbered colour labels Conform to standards ISO/IEC 11801 Ed. 2.0, draft amendment 2, EN 50173-2 and EIA/TIA 568 B2.10 19" panel - 1 U
1	335 73	STP - Metal shielding 360°

Pack	Cat.Nos	Modular panel
		Panel supplied with quick-fixing All enclosures or cabinets general assembly Panel ensures automatic grounding of each connector Fitted with rear cable guide to hold cables during maintenance Modular empty panel for up to 4 units Take the following equipment: - units of 6 x LCS ² RJ 45 connectors - telephone inlet units - fibre optic units - PoE injector units - video streaming units - switch units - telephone/Ethernet doubler units - copper/fibre optic converter units - blanking plates 19" panel - 1 U
1	335 90	

Pack	Cat.Nos	Units of 6 x RJ 45 connectors cat. 6A
		Fitted with 6 x LCS ² RJ 45 connectors cat. 6A with fast connection thanks to integrated crimping, with 568 A/B labelling Supplied with colour labels Conform to standards ISO/IEC 11801 Ed. 2.0, draft amendment 2, EN 50173-2 and EIA/TIA 568 B2.10
2	335 76	STP unit - metal shielding 360°
10	335 91	Blanking plate for 19" panel - Black